BANGALORE DIVISION.

The 30th September 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore division, up to 16th October 1897, for constructing a new High School at Channapatna. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 12 to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new High School at Channapatna", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing a New High School at Channapatna.

Items of works.	*Per.*	*Quantity.*
Clearing site and levelling ground	L. S.	Rs. 50
Earthwork excavation	C. yd.	346
Filling basement	„	178
Concrete	C. ft.	3,934
Burnt stone in chunam	„	5,813
Burnt brick in chunam	„	11,661
Do archwork	„	954
Slab stones	S. ft.	1,090
Plastering with chunam	Sqr.	175·86
Whitewashing	„	148·72
Color washing	„	54·63
Pointing with chunam	„	4·84
Flooring with concrete 4½" thick including smoothening	„	32·91
Flooring with Cuddapah slabs over 3" concrete with cement pointing ..	„	9·08
Bamboo matting	„	25·32
Cornice work with plaster (plain)	R. ft.	546
Moulding work with plaster	„	116
Do do	„	116
Do do	„	116
Ornamental parapet walls	„	142
Teakwood work with oiling	C. ft.	504·20
Roofing with 1st class Mangalore tiles and teak reepers	Sqr.	43·42
Flat terrace	„	11·34
Teakwood pannelled doors	S. ft.	1,030
Do windows venetianed outside and inside glazed and iron bars ..	„	444
Do venetianed with iron bars	„	235
Ventilators glazed	„	160
Circular ventilators	„	42
Finials, wooden	No.	6
Painting	Sqr.	33·48
Sun shades	No.	12
Zinc spouts	L. S.	Rs. 30
Constructing a latrine	L. S.	Rs. 300

B. S. Venkatachariyar, *Executive Engr.*